KADUR DIVISION.

Notification dated 22nd January 1938.

1. Sealed tenders will be received at the office of the Executive Engineer, Kadur Division, Chikmagalur up to 3 P.M. on 14th February 1938, for constructing a High Level Causeway at 4/8 of Mudgere-Belur Road and forming the deviation road approaches to High Level Causeway.

2. Tenders in the prescribed form obtainable in the office of the Executive Engineer, Kadur Division, Chikmagalur, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur and should be superscribed as "Tenders for constructing a High Level Causeway at 4/8 of Mudgere-Belur Road and forming the deviation road approaches." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender should be accompanied by a deposit of Rs. 300 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. Cash amount will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the dates at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, Kadur, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the office of the Executive Engineer, Kadur Division, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amount for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised, and if corrections are made the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for the current schedule of rates.

13. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Kadur Division and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities in estimates are only approximate and are liable to alteration, omissions, deductions or additions, at the discretion of the Executive Engineer, Kadur Division or his representative. The tendered rates will hold good for any quantity, whether it is higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and be handed over to the Public Works Department by the end of January 1939, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 100 which will be recovered from the contractor's outstandings, for the period exceeded by him over the time specified above.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer, Kadur Division, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Kadur Division, Chikmagalur.

19. No claims for damages for delays caused by officers of the Department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental Officers will be however considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Abstract estimate for constructing High Level Causeway at 4/8 of Mudigere-Belur Road and forming the deviation road approaches to High Level Causeway.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I. High Level Causeway at 4/8 of Mudigere-Belur Road.				
1	Earthwork excavation of foundations in hard soil including gravel and soft rock ..	C.yd.	..	80	
2	Benching in hard rock for piers, etc., 6″ to 1′ deep	S.ft.	..	472	
3	Laying burnt stone jelly in cement composite surki mortar 1 : 6 proportion	C.ft.	..	480	
3(*a*)	Do with broken quartz jelly ..	C.ft.	..	480	
4	Burnt size stone in surki mortar with bond stones complete	,,	..	1,900	
4(*a*)	Do in surki combination mortar 1 : 8 porportion	,,	..	1,900	
5	Cut waters of dressed stone in surki mortar ..	,,	..	39	
6	Cement pointing proportion 1 : 3 to masonry ..	Sqr.	..	7·37	
7	R.C.C. (1 : 2 : 4) deck slabs complete cast in situ with tension and compression reinforcements ½″ thick cement plastered 1 : 2 proportion and finished smooth including centring charges	C.ft.	..	660	
8	Providing expansion joints	R.ft.	..	15	
9	Providing and fixing dwarf R.C. pillars with holes for chains, etc., big	No.	..	4	
	Do small	,,	..	8	
10	Providing iron chains ½″ and removable iron uprights	R.ft.	..	128	
10(*a*)	New rough stone work with a lead of 1 mile ..	C.yd.	..	40	
11	Bonding iron hooks for holding down R.C.C. deck to masonry	No.	..	16	
12	Water diversion charges and bailing water during construction	L. S.	..	..	
13	Constructing of a 3′ vent culvert for the branch stream on existing road	,,	..	..	
	Total ..				...
	II. Forming the deviation road approaches to High Level Causeway.				
1	Earthwork excavation in hard soil and gravel to form road and side drains, etc., ..	C.yd.	..	2,274	
2	Collecting, breaking and stacking 1½″ blasted metal for new approach road in 4/8 average lead 2½ miles	C.yd.	..	55	
2(*a*)	Do quartz broken metal with lead	C.yd.	..	55	
3	2″ size quartz metal for soling complete hand packed to profile	C.yd.	..	111	
4	Collecting and stacking gravel with lead of 1 mile	,,	..	28	
5	Spreading and consolidating metal by steam roller	,,	..	55	
6	Spreading and consolidating gravel by steam roller	,,	..	28	
7	Collecting and spreading sand	,,	..	20	

Notification dated 24th January 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 14th February 1938 for constructing Reinforced Concrete Bridge across Yeechalahalla in $\frac{7}{8}$ of Mudgere-Byduvalli Road.

2. Tenders in the prescribed form, obtainable in the Office of the Executive Engineer, Kadur Division, Chikmagalur, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, and should be superscribed as "Tenders for constructing R.C.C. Bridge across Yeechalahalla in $\frac{7}{8}$ of Mudgere-Byduvalli Road". The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender should be accompanied by a deposit of Rs. 540 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. Cash amount will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, Kadur, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Kadur Division, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised, and if corrections are made the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Kadur Division, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities in estimates are only approximate and are liable to alteration, omissions, deductions or additions, at the discretion of the Executive Engineer, Kadur Division, or his representative. The tendered rates will hold good for any quantity whether it is higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and be handed over to the Public Works Department by the end of March 1939, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 100 which will be recovered from the contractor's outstandings for the period exceeded by him over the time specified above.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer, Kadur Division, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Kadur Division, Chikmagalur.

19. No claims for damages for delays caused by officers of the Department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental officers will be however considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the

Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Abstract estimate for the cost of constructing an R.C.C. Bridge across Yeechalahalla in $\frac{5}{8}$ of Mudgere-Byduvalli Road.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Jungle clearing	L.S.		..	
2	Earthwork excavation for foundations ..	C.yds.		288	
3	Stone jelly concrete in surki cement combination mortar 1 : 6 proportion	C.ft.		1,921	
4	Size stone in surki mortar with bond stones complete	,,		10,171	
4(a)	Do with surki combination mortar 1 : 8 proportion	,,		10,171	
5	Burnt stone slabs 6″ thick dressed roughly and fixed in mortar	Sq.ft.		28	
6	R.C.C. Beams cast in situ complete (1 : 2 : 4) as per design with exposed faces finished smooth including centering charges, etc., complete ..	C.ft.		462	
7	R.C.C. deck slabs (1 : 2 : 4) complete cast in with the beams and finished as per design including centering charges, etc., complete	,,		618	
8	Providing and fixing hand railings 2 ft. above road level with G.I. pipes and L iron uprights ..	R.ft.		150	
9	Bailing out water during construction ..	L.S.		..	
10	Providing expansion joints to R.C.C. decking ..	R.ft.		19	
11	Cement pointing 1 : 3 proportion	Sqr.		22·19	
12	Earthwork to embankment	C.yds.		567	
13	New rough stone work including lead ..	,,		231	
14	Collecting, spreading and consolidating 2″ jelly of quartz metal	,,		156	
15	Do $1\frac{1}{2}$″ quartz metal	,,		88	
16	Do gravel	,,		52	
17	Widening halla at Bridge site	L.S.		..	
18	Constructing masonry pedestals at ends ..	Nos.		4	

C. R. IYENGAR,
Executive Engineer.

INDIAN POSTS AND TELEGRAPHS DEPARTMENT.

OFFICE OF THE SUPERINTENDENT OF POST OFFICES, BANGALORE DIVISION.

Notice No. G.-18—2, *dated Bangalore the* 18*th January* 1938.

The attention of the public is invited to this office Notification No. G-18—2, dated the 22nd December 1937, calling for tenders for the conveyance of mails between Shimoga-Agumbe, *via*, Tirthahalli, published in pages 34 and 35, Part VI of the *Mysore Gazette*, dated the 6th January 1938.

Notice No. G.-21, *dated Bangalore the* 18*th January* 1938.

The attention of the public is invited to this office Notification No. G.-21, dated the 22nd December 1937, calling for tenders for the conveyance of mails between Shimoga P. O.—Shimoga R. S., published in pages 34 and 35, Part VI of the *Mysore Gazette* dated the 6th January 1938.